

AD-A058 511

O'BRIEN AND GERE ENGINEERS INC PHILADELPHIA PA JUSTIN--ETC F/6 13/2
NATIONAL DAM SAFETY PROGRAM. SILVER LAKE DAM (DE00041), MISPELL--ETC(U)
JUN 78 J J WILLIAMS


UNCLASSIFIED

DACW61-78-C-0052

NL

[OF]

AD
A058511



END

DATE

FILMED

11-78

DDC

ADA058511

LEVEL II



MISPILLION RIVER BASIN

MISPILLION RIVER, KENT COUNTY
DELAWARE

SILVER LAKE DAM

PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

Approved for public release;
distribution unlimited

DE 00041



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

JUNE 1978

AD No. _____
DDC FILE COPY

78 08 25 055 78 08 03 44

Best copy available per Hx. on file

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DE00041	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Silver Lake Dam Kent County, Delaware		5. TYPE OF REPORT & PERIOD COVERED (9) FINAL rept.
7. AUTHOR John J. Williams	(15)	6. PERFORMING ORG. REPORT NUMBER DACW61-78-C-0052
9. PERFORMING ORGANIZATION NAME AND ADDRESS O'Brien & Gere Engineers Inc. Justin & Courtney Div. 1617 J.F.K. Blvd. Philadelphia, Penna 19103		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS (12) 63p.
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106		12. REPORT DATE (11) June 78
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract) (6) National Dam Safety Program. Silver Lake Dam (DE00041), Mispillon River Basin, Mispillon River, Kent County, Delaware. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams-Del National Dam Safety Program Phase I Silver Lake Dam, Del		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO
NAPEN-D

28 JUL 1978

Honorable Pierre S. DuPont
Governor of Delaware
Dover, Delaware 19901

Dear Governor DuPont:

Inclosed is the Phase I Inspection Report for Silver Lake Dam in Kent County, Delaware which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given on the first three pages of the report.

Based on visual inspection, available records, calculations and past operational performance, Silver Lake Dam is judged to be in fair condition. However, the spillway is considered to be seriously inadequate. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

- a. Hydrologic and hydraulic investigations and engineering studies should be initiated within three months of the date of approval of this report to determine corrective action required to increase the capacity of the spillway to pass at least $\frac{1}{2}$ PMF. Construction of an improved spillway should commence in calendar year 1979. Due to the potential for overtopping of the dam, a detailed emergency operation, drawdown and warning system should be developed by the owner within the next two months.
- b. Monitoring of any changes in the structural condition of the railroad bridge abutments, which anchor the dam, should commence within three months of the date of approval of this report.
- c. Within nine months of the date of approval of this report, a stability analysis of arched spillway anchorages should be performed. Any remedial measures found necessary as a result of the stability analysis study should be initiated in calendar year 1979.

78 08 25 055

78 08 03 44

NAPEN-D

Honorable Pierre S. DuPont


d. Within one year of the date of approval of this report, trees and brush should be removed from the side slopes of the railroad embankment and a suitable controlled vegetation should be established.

A copy of the report is being furnished to Mr. Austin P. Olney, Delaware Department of Natural Resources and Environmental Control, the designated State Office contact for this Program. Within five days of the date of this letter, a copy will also be sent to Congressman Thomas B. Evans. Under the provisions of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, thirty days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia, 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely yours,



HARRY V. DUTCHYSHYN
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Cy Furn:
Mr. Austin P. Olney, Secretary
Department of Natural Resources and
Environmental Control

LEVEL II

PHASE I REPORT

NATIONAL DAM SAFETY PROGRAM

Name of Dam: Silver Lake Dam

State Located: Delaware

County Located: Kent County

Stream: Mispillion River

Date of Inspection: May 25, 1978

ASSESSMENT OF GENERAL CONDITIONS


Silver Lake Dam consists of a steel sheet pile spillway with massive railroad bridge abutments and embankments forming the non-overflow section.

Visual inspection of the spillway steel sheet piling revealed no serious structural deficiencies. However, the structural condition of the railroad bridge is poor. A recently constructed highway bridge is located immediately downstream of the railroad bridge. This highway bridge appears to be in good condition and would act as a stabilizing factor in the event of failure of the railroad bridge. A stability analysis should consider the structures (spillway, railroad bridge and highway bridge) acting in series. This stability analysis is beyond the scope of a Phase I Report.

ACCESSION for	
NTIS	White Section <input checked="" type="checkbox"/>
CON	Buff Section <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION.....	
BY.....	
DISTRIBUTION/AVAILABILITY CODES	
DATE APRIL 25, 1978	
A	

Hydraulics/Hydrologic analyses reveal that the embankments would be overtopped for all storms exceeding approximately fourteen (14) per cent of Probable Maximum Flood (PMF); therefore, the spillway can be considered "seriously inadequate" as cited in Engineering Technical Letter No. 1110-2, January 25, 1978. In order to satisfy criteria established by the Department of the Army, Office of the Chief of Engineers, remedial measures that should be considered include increasing the length of the spillway structure and providing an additional waterway to pass at least $\frac{1}{2}$ PMF without overtopping the embankments.

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION


John S. Williams, P.E.
Vice President

Based on visual inspection, available records, calculations and past operational performance, Silver Lake Dam is judged to be in fair condition. However, the spillway is considered to be seriously inadequate. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. Hydrologic and hydraulic investigations and engineering studies should be initiated within three months of the date of approval of this report to determine corrective action required to increase the capacity of the spillway to pass at least $\frac{1}{2}$ PMF. Construction of an improved spillway should commence in calendar year 1979. Due to the potential for overtopping of the dam, a detailed emergency operation, drawdown and warning system should be developed by the owner within the next two months.

b. Monitoring of any changes in the structural condition of the railroad bridge abutments, which anchor the dam, should commence within three months of the date of approval of this report.

c. Within nine months of the date of approval of this report, a stability analysis of arched spillway anchorages should be performed. Any remedial measures found necessary as a result of the stability analysis study should be initiated in calendar year 1979.

d. Within one year of the date of approval of this report, trees and brush should be removed from the side slopes of the railroad embankment and a suitable controlled vegetation should be established.

APPROVED:

Harry V. Dutchyshyn

HARRY V. DUTCHYSHYN
Colonel, Corps of Engineers
District Engineer

DATE:

28 July 1978



OVERALL VIEW OF DAM



VIEW OF DAM AND RAILROAD BRIDGE

TABLE OF CONTENTS

<u>TEXT</u>	<u>PAGE</u>
Assessment of General Conditions	
Section 1 - Project Information	1-3
Section 2 - Engineering Data	4
Section 3 - Visual Inspection	5-6
Section 4 - Operational Procedures	7
Section 5 - Hydraulic/Hydrologic	8
Section 6 - Structural Stability	9-10
Section 7 - Assessment/Remedial Measures	11

FIGURES

Figure 1 - Regional Vicinity Map
Figure 2 - Geologic Map
Figure 3 - Silver Lake Spillway, Milford, Delaware (design drawing)

APPENDIX

Photographs	A-1 - A-4
Field Inspection Report	A-5 - A13
Hydrologic and Hydraulic Calculations	A-14 - A-37

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
NAME OF DAM SILVER LAKE DAM ID# DE 00041

SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - This report is authorized by the Dam Inspection Act, Public Law 92-367, and has been prepared in accordance with contract #DACW61-78-C-0052 between O'Brien and Gere Engineers, Justin and Courtney Division, and the United States Army Corps of Engineers, Philadelphia District.

b. Purpose of Inspection - The purpose of this inspection is to evaluate the structural and hydraulic condition of Silver Lake Dam and appurtenant structures, and to determine if the dam constitutes a hazard to human life or property.

1.2 PROJECT DESCRIPTION

a. Description of Project - The spillway is a semi-circular sheet pile overflow structure approximately ninety (90) feet in length. The sheeting section is anchored at each end by massive concrete abutments of a railroad bridge which was constructed in the year 1913. Immediately downstream, the railroad bridge is adjoined by a newly constructed highway bridge.

According to a design drawing (see Figure 3) provided by the Delaware Department of Natural Resources and Environmental Control (DDNREC), Division of Soil and Water Conservation, a sloping clay blanket rests against the upstream face of the vertical sheeting.

The downstream slope of the spillway is protected with a concrete apron. The apron extends through the waterway passage of the railroad bridge and terminates upstream of the highway bridge at an area of dumped riprap.

A forty-eight inch diameter pipe is located through the sheeting on the left (looking downstream) side of the dam. The plan indicates that flow through this pipe is controlled by means of baffle boards that can be installed manually.

b. Location - Silver Lake Dam is located on the Mispillion River in Milford, Kent County, Delaware. The reservoir formed by the dam extends to the Haven Lake Dam which is located about one-half mile upstream.

c. Size Classification - According to the design drawing and data provided, the maximum height of the spillway is ten (10) feet; the reservoir storage at the spillway crest is approximately 60 acre-feet. In accordance with the Recommended Guidelines for Safety Inspection of Dams, Silver Lake Dam is in the small size category.

d. Hazard Classification - Due to urban development downstream of the dam, a significant number of human lives could be in jeopardy should the dam fail. Therefore, in accordance with the Recommended Guidelines for Safety Inspection of Dams, Silver Lake Dam is in the high hazard potential category.

e. Ownership - The dam is owned by the DDNREC and operated by the Division of Fish and Wildlife.

f. Purpose of Dam - According to DDNREC, Division of Soil and Water Conservation, the purposes of the dam are flood control, water supply and recreation.

g. Design and Construction History - The spillway was designed by the Delaware State Highway Department for the DDNREC, Division of Fish and Wildlife, and construction was completed in 1964.

h. Normal Operational Procedures - The reservoir is maintained at a fixed level. According to DDNREC, Division of Soil and Water Conservation, the 48 inch diameter discharge pipe is not being used.

1.3 PERTINENT DATA (From data furnished by DDNREC, Division of Soil and Water Conservation and the United States Army, Corps of Engineers)

a. Drainage Area - The drainage area determined from United States Geological Survey (USGS) Quadrangle Maps is about 30 square miles.

b. Discharge at Damsite - No records of maximum discharge were made available.

c. Elevation (feet above MSL)

Top of Spillway - 6.65

Streambed at Dam - 0.65

Invert of Reservoir Drain - 0.65 (48-inch diameter pipe)

Top of Railroad Embankment - 13 (estimated)

d. Reservoir Data (Water Surface Elevation at Spillway Crest)

Storage - 60 acre- feet

Area - 30 acres (from USGS Quad Sheet)

e. Spillway

Type - Steel Sheet Pile

Length - 90 feet

Structural Height - 10 feet

Slopes - Upstream $1\frac{1}{2}$ Horizontal to 1 Vertical
(estimated from plans)

Slopes - Downstream - 2 Horizontal to 1 Vertical
(estimated from plans)

f. Regulating Outlet

48-inch diameter pipe, invert elevation 0.65 feet

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

A design drawing was provided by the DDNREC, Division of Soil and Water and is reproduced herein as Figure 3.

2.2 CONSTRUCTION

No construction information was made available.

2.3 OPERATION

According to the DDNREC, Division of Soil and Water, the reservoir is maintained at a fixed level. The 48-inch diameter reservoir drawdown pipe is not operated under normal conditions.

2.4 EVALUATION

Design calculations relative to the dam are unavailable.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General - The visual inspection of Silver Lake Dam was conducted on May 25, 1978. The depth of water flowing over the spillway at the time of inspection was about 0.2 feet. The weather was clear and the temperature was about sixty degrees. No underwater areas were inspected.

b. Spillway - The spillway is constructed of steel sheeting placed in a semi-circle. The sheeting is in good condition: horizontal and vertical alignment indicate no apparent movement in the structure. The concrete apron on the downstream side of the spillway appears to be free from cracks and spalls in the portions visible. However, a depression at the center of the apron was noted during the inspection. This depression is not indicated on the design plan. The plan, however, does indicate a notch in the sheeting which was not observed during the inspection.

The 48-inch diameter pipe located on the left side of the spillway was not discharging at the time of inspection. The baffle boards which control flow through this pipe could not be observed due to the water level.

c. Non-Overflow Section - The spillway is anchored by the concrete wing walls of a railroad bridge; the interconnection between the sheet piling and the wing wall is made by placement of a concrete plug at both ends of the spillway. The concrete plugs appear to be in good condition; no seepage was observed at the joints.

The wing walls of the railroad bridge show significant deterioration and structural stress. Concrete aggregate is exposed on the top surface of the wing walls and major horizontal and vertical cracks extend throughout the wing walls and endwalls of the concrete abutments. Aggregate is exposed in the walls in the lower half of the vertical height.

A new concrete highway bridge, which appears to be in excellent condition, is located immediately downstream of the railroad bridge. Three corrugated metal pipe arches, each with a span of about fifteen feet, form the waterway under this bridge.

The earth embankment portions of both bridges appear to be in good condition. Although the slopes are unprotected, no indication of seepage, erosion or instability were noted.

d. Reservoir Area - The reservoir perimeter is sparsely developed and supports a dense growth of brush and trees. No indication of slope instability was noted during the inspection.

e. Downstream Channel - The left bank of the outlet channel downstream of the highway bridge is lined with steel sheet piling for a distance of about three hundred feet. The right bank in the same area is protected with broken concrete slabs which serve as riprap slope protection. Commercial establishments are located on the property adjacent to both banks. Further downstream, the channel continues through the community of Milford.

The Mispillion River downstream of the dam is subject to the tidal influence of the Delaware River.

3.2 EVALUATION

No significant deficiencies relative to the spillway were noted during the Phase I Visual Inspection.

The concrete wing walls supporting the railroad bridge abutments show indications of structural stress. However, the recently constructed highway bridge located immediately downstream of the railroad bridge appears to be in good condition and may act as a second dam in the event of failure of the railroad bridge.

SECTION 4 - OPERATIONAL PROCEDURES

According to the DDNREC, Division of Soil and Water, the reservoir is maintained at a fixed level. The 48-inch diameter low level discharge is closed and is currently not in use. A review of the design plan indicates that handles are provided on the baffle boards to allow for manual removal. No flood warning system is in existence.

SECTION 5 - HYDRAULIC/HYDROLOGIC

In accordance with the Recommended Guidelines for Safety Inspection of Dams, the Spillway Design Flood used to evaluate the hydraulic capabilities of Silver Lake Dam is the Probable Maximum Flood (PMF). The PMF was estimated from probable maximum precipitation data published in Hydrometeorological Report No. 33.

Rainfall data was modified to reflect storm pattern and basin size by using standard factors. Snyder coefficients were provided by the Department of the Army, Philadelphia District, Corps of Engineers. This data was developed and entered into the HEC-I computer program.

Due to the relationship between Haven Lake Dam (DE 00042) and Silver Lake Dam, the reservoirs were routed in series: the discharge hydrograph for Haven Lake Dam being used as the inflow hydrograph to Silver Lake Dam. The additional drainage area contributing to Silver Lake is about 0.6 square miles. It is not considered significant to the analysis.

The flood routing performed indicated that the maximum discharge is about 44,700 cfs and that the railroad embankment would be overtopped by a maximum depth of about 10 feet. The duration of overtopping is about fourteen (14) hours. This is based on the assumption that no other overflow areas exist along the shoreline. Further analysis reveals that the embankments would be overtopped for all storms exceeding approximately fourteen (14) per cent of PMF.

A drawdown analysis was performed to determine the time required to drain the reservoir. The 48-inch diameter pipe was used as the discharge structure for this analysis. The crest elevation was assumed as the starting water elevation and inflow was considered to be negligible. Under these conditions, the estimated time to drain the reservoir is thirteen (13) hours. This represents a minimum time with no consideration given to downstream constraints such as safe discharge velocities or flows.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observation - No indications of structural stress were evident during the inspection of the sheet piling spillway. A depression in the apron downstream of the center of the sheeting was noted, but it could not be determined whether this was by design or due to foundation settlement.

The concrete walls of the railroad bridge abutments which anchor the spillway sheet piling appear to be in poor structural condition.

b. Design and Construction Data- A design drawing was provided by the DDNREC, Division of Soil and Water Conservation. Design data and information relative to the hydrologic and hydraulic computations are not available.

c. Operating Records - Operating records were not made available.

d. Post Construction Changes - No post construction changes have been reported.

e. Seismic Stability - Silver Lake Dam is located on the Mispillion River in the Atlantic Coastal Plain physiographic province. The topography reveals a gently, rolling land surface with elevations ranging from sea level to about sixty feet (MSL). Foundation materials consist of recent alluvium deposits and silty to clayey sands and granular unconsolidated sediments of the Pleistocene Columbia formation. Bedrock is not a consideration for foundation conditions at this location.

The site is located within zone one as shown on the Seismic Zone Map of Contiguous States. Projects located in this zone require no earthquake analysis provided they are not within the influence area of an active fault.

f. Evaluation - The stability of the dam is dependent in part upon the ability of the massive railroad bridge abutments to support the steel sheeting. The structural condition of the concrete walls of the railroad bridge is poor. Additional stability analysis should consider the three structures (spillway, railroad bridge and highway bridge) acting in series.

Hydrological and hydraulic studies indicate that the PMF would overtop the embankment for a considerable period of time. It is reasonable to assume that the embankments were not designed to withstand an overtopping condition. The possibility of embankment failure under this circumstance is significantly increased by the period of time that the embankment is exposed to overtopping. A stability analysis of the railroad bridge structure and evaluation of embankments under these conditions is beyond the scope of a Phase I Report.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety - The spillway is hydraulically inadequate to pass the PMF without overtopping the railroad bridge embankments; the estimated capacity of the spillway is about fourteen (14) per cent of the PMF. During the period of overtopping, failure of the railroad embankment is a possibility.

b. Adequacy of Information - Information relative to the structural design of the spillway and railroad is unavailable.

c. Urgency - Further Hydrological/Hydraulic evaluation of the dam is recommended within a reasonable period of time.

d. Additional Investigations - Hydrological/Hydraulic studies should be made to determine the additional discharge capacity necessary to pass at least the $\frac{1}{2}$ PMF without damaging the railroad embankments.

7.2 REMEDIAL MEASURES

a. Remedial measures that should be considered include increasing the length of the spillway structure and providing an additional waterway passage to pass at least $\frac{1}{2}$ PMF without overtopping of the embankments.


b. O&M Maintenance and Procedures - A regular maintenance program should be established to:


Monitor any changes in the structural condition of the railroad bridge

Regularly operate the regulating mechanism on the discharge pipe

Maintain a controlled vegetation cover on the sideslopes of the railroad embankment.

FIGURES





LEGEND










- | | | | |
|---|--|--|-------------|
|  | AM24- Sandy and silty soil |  | Milford, DE |
|  | AM2 - Sandy soil | | |
|  | AM2/24- Sandy soil with some silt | | |
|  | AM23 - Sandy soil, poorly graded | | |
|  | AR-Z- Alluvial gravel, sand, silt and clay; rich in organic material | | |
|  | AM12/23- Gravelly, sandy soil; poorly graded | | |


FIGURE 2
GEOLOGIC MAP



Excavate small channel-
to ensure flow toward pipe
(Item 2)



Scale: 1" = 10'-0"





ELEV. H-H

(Top of Sheeting stepped down)
Scale: $\frac{1}{2}'' = 1'-0''$

Scale: $\frac{1}{2}'' = 1'-0''$



Pipe to be
attached w/
clamps or w/

Scale: $\frac{1}{2} = 1.0^\circ$ 

Scale: 1" = 10'-0"


QUANTITIES, PAY ITEMS				
ITEM	DESCRIPTION	UNIT	AMOUNT	PROPOSED
2	Excavation	C.Y.	30	80
7	Select Borrow	C.Y.	308	350
15	Portland Cement Concrete Pavement	C.Y.	79	85
21	Wire Mesh Reinforcement	S.F.	4200	4200
29	48" Corrugated Metal Pipe (let)	L.F.	16	16
---	Steel Sheet Piles	L.F.	1660	1915
---	Control Gate and Assembly		1.5	1.5
---	Clay Blanket (6")	S.Y.	133	150
64	Dumped Rip Rap	Ton	2.5	35

COUNTY	CONTRACT	C.R. & R.R. NO.	STATE	FED. AID PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
KENT & SUSSEX	64-02-001	2	DEL.		1964	1	1



SILVER LAKE SPILLWAY, MILFORD, DEL.

NOTES


Location: In the City of Milford on Maple Ave.
Specifications: Standard Specifications of DSHD
Special Provisions of this contract.



SECT. D-D
Scale: 1/2" = 1'-0"




PLAN AT MILL RACE (on Mill St.)
Scale: 1" = 30'




SECT. K-K
Scale: 1/4" = 1'-0"


ELEV. E-E



HANDLE DETAIL
(put one on each board)



LOCATION PLAN
Scale: 1" = 1200'



SECTION B-B
Scale: 1" = 10'-0"

Build steel sheet pile spillway & reinf. conc. apron

Silver Lake

KENT COUNTY


MILFORD

Del Game & Fish Comm.

SUSSEX COUNTY

Spillway

N



PLAN - MAPLE AVE.
Scale: 1" = 30'

FIGURE 3

C. Powell Smith
CHIEF PLANNING & DESIGN DIV.

ASSISTANT CHIEF ENGINEER

Joe S. Calvine
Asst. CHIEF ENGINEER

Director of Operations

RECOMMENDED January 24, 1964

RECOMMENDED 196

APPROVED 1/24 1964

APPROVED 1-24 1964


DELAWARE STATE HIGHWAY DEPARTMENT		
SILVER LAKE SPILLWAY MILFORD, DEL.		
D. RBS T. A.W.R. C.B. 1/1/64	SCALE As Noted	APPROVED BY BRIDGE ENGINEER

ITEMS	QUANTITY	PROPOSAL
C.V.	30	80
C.T.	308	350
C.L.	19	85
S.P.	4200	4200
L.P.	16	16
L.P.	1660	1915
L.S.	15	15
S.V.	135	150
Ton	2.8	10 Tons

APPENDIX

PHOTOGRAPHS

A-1



DEPRESSION AT CENTER OF DAM



DISCHARGE PIPE AT LEFT ABUTMENT OF DAM


A-2

78 08 03


44



CRACK IN RAILROAD BRIDGE WINGWALL (LEFT ABUTMENT)



VIEW OF CRACK AND EXPOSED AGGREGATE IN RAILROAD
BRIDGE ENDWALL (RIGHT ABUTMENT)



FLOW AT DOWNSTREAM HIGHWAY BRIDGE



VIEW OF DOWNSTREAM CHANNEL

FIELD INSPECTION REPORT

Check List
Visual Inspection
Phase 1

Name Dam Silver Lake Dam County Kent State Delaware Coordinators Mr. Krishna Patel, Division Engineer

Date(s) Inspection May 25, 1978 Weather Sunny Temperature 65°

Pool Elevation at Time of Inspection 6.25± M.S.L. Tailwater at Time of Inspection N/A M.S.L.

Inspection Personnel:

Mr. George C. Elias _____

Mr. Frank E. Falcone _____

Mr. Richard E. Horvath _____

Mr. Richard E. Horvath Recorder

Accompanied by:

Mr. Krishna G. Patel, Division Engineer, Delaware Department of Natural Resources
and Environmental Control, Division of Soil and Water Conservation.

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SEE PAGE ON LEAKAGE

STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS

No seepage or erosion was evident at the structure/embankment junction. The spaces between the sheeting and concrete bridge abutment walls appear to be effectively closed by concrete plugs.

DRAINS

None noted.

A-7

WATER PASSAGES

No indication of erosion or cracks were observed in the concrete apron of the spillway.

A depression in the concrete apron was observed. No depression was shown on the plans.

FOUNDATION

Not observed.

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	No cracking was noted in the concrete portion of the spillway. However, significant cracking and spalling were noted in the wingwalls and endwalls of the supporting railroad bridge abutment.	
STRUCTURAL CRACKING	Significant structural cracking was noted in the concrete wingwalls and endwalls of the supporting railroad bridge abutment.	
VERTICAL AND HORIZONTAL ALIGNMENT	Vertical and horizontal alignment of the steel sheeting appeared to be good.	
MONOLITH JOINTS	N/A	
CONSTRUCTION JOINTS	Concrete plugs were apparently cast directly against the existing concrete wingwalls of the railroad bridge. No joint material was observed in the joints. No movement was evident along the joints.	

EMBANKMENT

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

SURFACE CRACKS

None Noted.

UNUSUAL MOVEMENT OR
CRACKING AT OR BEYOND
THE TOE

None Noted.

SLOUGHING OR EROSION OF
EMBANKMENT AND ABUTMENT
SLOPES

None Noted.

A-9

VERTICAL AND HORIZONTAL
ALIGNMENT OF THE CREST

The alignment of the railroad
embankment showed no indication
of settlement and appeared to be
in line horizontally.

RIPRAP FAILURES

N/A

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	No cracking or spalling was observed in the portions of the concrete apron visible.	
INTAKE STRUCTURE	Not observed.	
OUTLET STRUCTURE A-10	N/A.	
OUTLET CHANNEL	The slopes of the outlet channel are protected for about 400 feet downstream; steel sheeting on the left bank, broken concrete slabs on the right bank.	
EMERGENCY GATE	N/A	

UNCATED SPILLWAY

REMARKS OR RECOMMENDATIONS

VISUAL EXAMINATION OF

OBSERVATIONS

SHEETPILE WEIR

The steel sheeting which forms the crest shows only minor signs of corrosion.

APPROACH CHANNEL

N/A

DISCHARGE CHANNEL

N/A

A-11

BRIDGE AND PIERS

N/A

7

RESERVOIR

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

SLOPES

The reservoir slopes are well covered with vegetation and no erosion or slope failure was noted.

SEDIMENTATION

The degree of sedimentation could not be determined.

DOWNSTREAM CHANNEL

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

The channel immediately downstream of the spillway is constricted by the crossing of two bridges.

CONDITION
(OBSTRUCTIONS,
DEBRIS, ETC.)

SLOPES

The channel slopes are protected by steel sheeting and broken concrete slabs for a distance of about 400 feet downstream.

APPROXIMATE NO.
OF HOMES AND
POPULATION

The downstream channel flows through the community of Milford, Delaware. The population of Milford is about 5,700.

HYDROLOGIC AND HYDRAULIC CALCULATIONS

SUBJECT

SILVER LAKE DAM

SHEET

1

BY

R.E.H.

DATE

5/25/70

JOB NO

1800 001 21

PME COMPS

Drainage Area = 30 sq miles

From USGS Quad Sheet

7 1/2 MIN series

PMP - 6 hr duration, 10 sq miles zone 6
= 28"

- Isohyetal "fit" reduction factor = 17.5 %

- Depth - Area - Duration adjustment = 91 %

adjusted PMP $\Rightarrow [28" - 17.5(28")] \cdot .91 = 21"$

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC



SUBJECT	SHEET	BY	DATE	JOB NO.
SILVER LAKE DAM	2	REH	5/29/78	1800 001.12

TIME (Hrs)	% 6 hr PMP	Σ 6 Hr PMP	Incr PMP	
.5	.30	6.3	6.3	①
1.0	.50	10.5	4.2	②
1.5	.58	12.2	1.7	③
2.0	.65	13.7	1.5	④
2.5	.70	14.7	1.0	⑤
3.0	.75	15.8	1.1	⑥
3.5	.80	16.8	1.0	⑦
4.0	.85	17.9	1.1	⑧
4.5	.88	18.5	.6	⑨
5.0	.93	19.5	1.0	⑩
5.5	.96	20.2	.7	⑪
6.0	1.00	21.0	.8	⑫

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

SUBJECT

SILVER LAKE DAM

SHEET

3

BY

REI+

DATE

5/29/78

JOB NO

1800001 199

	RAINFALL		RUNOFF		LOSSES	
	E	INC	E	INC	E	INC
5	.6	.6	0	0	.6	.6
10	1.3	.7	0	0	1.3	.7
15	2.1	.8	.3	.8	1.8	.5
20	3.2	1.1	.8	.5	2.4	.6
25	4.3	1.1	1.5	.7	2.8	.4
30	5.8	1.5	2.6	1.1	3.2	.4
35	10.0	4.2	6.2	3.6	3.8	.6
40	16.3	6.3	12.1	5.2	4.2	.4
45	18.0	1.7	13.7	1.6	4.3	.1
50	19.0	1.0	14.7	.9*	—	.1*
55	20.0	1.0	15.6	.9	—	.1
60	21.0	1.0	16.6	.9*	—	.1*

* Assume minimum loss rate

= .2" / hr

CN = 70

Snyder's Parameters

$C_t = .9$ and $640 C_p = 310$ - Provided by the Dept of

$L = 8.7$ miles $L_{CA} = 4.35$ miles the Army, Pinal Dist., Corps of

$T_p = C_t (L L_{CA})^{.3} = 2.68$ Engrs

$C_p = .48$

SUBJECT	SHEET	BY	DATE	JOB NO
SILVER LAKE DAM	4	REL	5/29/78	1800.001 1.30

STAGE - STORAGE

From USGS Quadrangle
Sheet, 7 1/2 min. series

Area @ El. 9 = 30.3 Ac - Assume spillway crest

Area @ El. 10 = 45.9 Ac

$$\frac{\Delta \text{Area}}{\Delta \text{El}} = 15.6 \text{ Ac/Ft}$$

Assume Area varies linearly with stage

$$A = (45.9 - 30.3) d + 30.3$$

$$= 15.6 d + 30.3$$

$$S = \int A$$

$$\therefore \text{Storage} = 7.8 d^2 + 30.3 d$$

STAGE	d (Ft)	STORAGE (AcFt)
6.65	0	0
8.65	2	91.8
10.65	4	246.0
12.65	6	462.6
14.65	8	741.6
16.65	10	1083.0
17.0	10.35	1149.2
19.0	12.35	1563.9
21.0	14.35	2041.0
24.0	17.35	2874.0

JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 5 OF


DATE 5/29/78

COMP. BY REL

CHECKED BY

NAME OF CLIENT Corps of Engrs

PROJECT Silver Lake Dam



(+) A-19
ST

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC



THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

SUBJECT	SHEET	BY	DATE	JOB NO
SILVER LAKE DAM	6	REIN	5/19/78	1800.001 -1

STAGE - DISCHARGE RELATIONSHIP - Dam Spillway

$$Q = CLH^{3/4}$$

ASSUME $C = 3.5$

$$L = 90'$$

$$Q = 315 H^{3/2}$$

ASSUME 48" dia pipe to be closed

Elev	Head (ft)	Discharge (cfs)
6.65	0	0
7.0	.35	65
7.5	.85	246
8.0	1.35	494
8.5	1.85	793
9.0	2.35	1135
9.5	2.85	1516
10.0	3.35	1931
10.5	3.85	2380
11.0	4.35	2858
11.5	4.85	3365
12.0	5.35	3898
13.0	6.35	5040

A-20

SUBJECT

SILVER LAKE DAM

SHEET

6A

BY

REH

DATE

6/14/78

JOB NO

1800 001-199

STAGE - DISCHARGE RELATIONSHIP

-RAILROAD BRIDGE

E1 13 Top of Embankment Elevations are estimated
E1 9.5 Low Chord from plan drawing

E1 0.65 invert

Flow Area = $40 \times 9 = 360'$

$W_p = 98$

$$H = \left(1 + K_e + \frac{29 H^2 L}{r^{1.33}} \right) \frac{V^2}{2g}$$

$r = 367 \quad r^{1.33} = 5.64'$

$L = 20'$

$$V = \sqrt{42.4 H}$$

$n = .015$

$K_e = .5$

Assume $TN = 2.5'$

Elev	H	V	Q (cfs)
13	3.5	12.2	4392
12	2.5	10.3	3708
11	1.5	8.0	2880
10	.5	4.6	1656

↑
control

For simplification, the spillway has been assumed to control up to elev 11.0 (no tailwater is considered). Above elev 11.0 pressure and weir flow (relative to the railroad bridge) are assumed to control (a tailwater^{elev.} equal to 9.5 was used).

$$Q_{weir} = C L H^{3/2} = 3(400) H^{3/2} = 1200 H^{3/2}$$

A-21

SUBJECT	SHEET	BY	DATE	JOB NO.
SILVER LAKE DAM	63	RE 4	6/14/78	1800.001 9

Pressure Flow				WEIR FLOW		
Flow	Hp	$V=1$ (fps)	D_s (cfs)	Hw	D_s (cfs)	D_s (total)
14	4.5	13.8	4968	1	1200	6168
15	5.5	15.3	5508	2	3394	8902
16	6.5	16.6	5976	3	6235	12211
17	7.5	17.3	6408	4	9600	16008
18	8.5	19.0	6840	5	13416	20256
19	9.5	20.1	7236	6	17636	24872
20	10.5	21.1	7596	7	22224	29820
21	11.5	22.1	7956	8	27153	35109
22	12.5	23.0	8280	9	32400	40680
23	13.5	23.9	8604	10	37947	46551
24	14.5	24.8	8928	11	43779	52707


COMPUTER INPUT

STAGE	6.5	7	9	11	13	15	17	19	21	24	Ft
STORAGE	0	12	114	279	507	780	1149	1564	2041	2874	1 Ft
DISTANCE	0	65	1135	2858	4392	8902	16008	24872	35109	52707	CFS

JUSTIN & COURTNEY, INC.
 Division of O'Brien & Gere Engineers, Inc.
 PHILADELPHIA, PA


SHEET NO. 6C OF
 DATE 6/14/78
 COMP. BY REH
 CHECKED BY

NAME OF CLIENT CORPS of ENGRS
 PROJECT SILVER LAKE DAM



THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

SILVER LAKE DAM
% PMF VS STORAGE



SUBJECT

SILVER LAKE DAM

SHEET

7

BY

REH

DATE

6/7/78

JOB NO

1300 001 199

Cl. closed DEC

RESERVOIR DRAWDOWN ANALYSIS


Storage @ spillway crest = 60 Ac Ft

Surface area @ Crest = 30 Ac

Depth of water @ spillway = $6.65 - 0.65 = 6'$

Assume surface area @ el 0.65 = 0 Ac

Section through lake (assume $d_1 = 2'$)



$$\text{Storage} = \frac{(30+X)(2)}{2} + \frac{X(4)}{2}$$

$$60 = 30 + X + 2X$$

$$30 = 3X$$

$$X = 10 \text{ Ac}$$

Elev	Area (Ac)
6.65	30
5.65	20
4.65	10
3.65	7.5
2.65	5.0
1.65	2.5
0.65	0

SUBJECT	SHEET	BY	DATE	JOB NO
SILVER LAKE DAM	8	DEH	6/7/78	1800 001 09

Checked DBC

Begin drawdown @ elevation 6.65

Assume no tailwater condition, no inflow

EL	Area (Ac)	($\text{cf} \times 10^6$) INCREMENTAL Storage	(ft) HW	(cfs) * Q	(cfs) Q _{AVE}	(hrs) Time
6.65	30		6	115		
		1.742			95	5.0
4.65	10		4	75		
		.653			50	3.6
2.65	5		2	25		
		.218			13	4.7
0.65	0		0	0		

13.3 hrs

Minimum drawdown time \approx 13 hrs

* Discharges determined from culvert capacity charts published by the Bureau of Public Roads (1/63) and presented in "Handbook of Concrete Culvert Pipe Hydraulic Assume inlet control, headwall entrance.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

HEG-1 VERSION DATED JAN-1973
UPDATED AUG 74
CHANGE NO. 01

PMF ROUTING
HAVEN LAKE DAM AND SILVER LAKE DAM
OARREN + GERE - JUSTIN AND COURTNEY DIV

JOB SPECIFICATION
NO NHR NMIN IDAY IHR IMIN MEIPC IPLT IPRT NSTAN
48 0 30 1 0 0 0 0 2 0
JOPER NMT
5 0

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .10 .20 .30 .40 .50 .60 .70 .80 1.00
NPLAN= 1 NRTIO= 9 LRTIO= 1

SUB-AREA RUNOFF COMPUTATION

ISIAQ ICOMP IECON ITAPE JPLT JPRT INAME
1 0 0 0 1 0 0

HYDROGRAPH DATA

IHYDG IJHG TAREA SNAP TRSOA TRSPC RATIO ISNOW ISAME LOCAL
0 1 30.00 0.00 0.00 0.00 0.00 0 1 0

PRECIP DATA

NP STORM DAJ OAK
12 0.00 0.00 0.00

PRECIP PATTERN

0.00 0.00 .30 .50 .70 1.10 3.60 5.90 1.60 .90
90

LOSS DATA

STKR DLTKR RTIOL FRAIN STRKS RTIOX STRTL CNSTL ALSNX RTIMP
0.00 0.00 1.00 0.00 0.00 1.00 0.00 0.00 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 2.70 CP= .46 NTA= 0

RECESSION DATA

STRIQ= 0.00 QRCSN= 0.00 RTIOR= 1.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 5.84 AND R= 7.77 INTERVALS

UNIT HYDROGRAPH 45 END-OF-PERIOD ORDINATES, LAG= 2.70 HOURS, CP= .46 VOL= 1.00

234.	869.	1746.	2626.	3250.	3443.	3208.	2820.	2479.	2179.
1916.	1684.	1481.	1302.	1146.	1006.	844.	777.	643.	601.
528.	464.	408.	359.	315.	277.	244.	214.	188.	166.
146.	128.	112.	99.	87.	76.	67.	59.	52.	46.
40.	35.	31.	27.	24.					

END-OF-PERIOD FLOW

TIME RAIN EXCS COMP Q
0 0 0 0 0 0 0 0 0 0

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

A-28

THIS PAGE IS BEST QUALITY PRACTICE
FROM COPY FURNISHED TO DDC

	SUM	16.40	16.40	629809.
PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
48280.	36419.	13121.	13121.	629812.
	11.29	16.27	16.27	16.27
	18058.	26039.	26039.	26039.

[illegible]

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

0000

0000

0000

0000

0000

0000

0000

0000

0000

0000

0000

0000

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
33796. 25493. 9145. 440869.
JFS 7.90 11.39 11.39 11.39
INCHES 12648. 18227. 18227. 18227.
AC-FT

HYDROGRAPH-AT STA 1-FOR PLAN 1, RTIO-8
0. 56. 302. 898. 2021. 4247. 8740. 15706. 23831.
31331. 36584. 37731. 35286. 32250. 28903. 25539. 22451. 19737.
17351. 15253. 13409. 11707. 10362. 9109. 8008. 7040. 5440.
4783. 4204. 3696. 3249. 2856. 2511. 2207. 1940. 1500.
1318. 1159. 896. 787. 692. 608. 530.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
38624. 29135. 10497. 503850.
CFS 9.03 13.02 13.02 13.02
INCHES 14455. 20831. 20831. 20831.
AC-FT

HYDROGRAPH-AT STA 1-FOR PLAN 1, RTIO-9
0. 70. 378. 1122. 2526. 5309. 10925. 19632. 29789.
39164. 45731. 48280. 47164. 44108. 40313. 36129. 31924. 24671.
21688. 19066. 16761. 14734. 12953. 11387. 10010. 8800. 6800.
5978. 5255. 4620. 4061. 3570. 3139. 2759. 2426. 2132.
1648. 1449. 1273. 1119. 984. 865. 761. 662.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
48280. 36419. 13121. 629812.
CFS 11.29 16.27 16.27 16.27
INCHES 18068. 26039. 26039. 26039.
AC-FT

A-30

HYDROGRAPH ROUTING
ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME
2 1 0 0 0 0 0
ROUTING DATA
QLOSS CLOSS AVG IRES ISAME
0.0 0.000 0.00 1 1

NSTPS NSTDL LAG ANSKK X TSK STORA
1 0 0 0.000 0.000 0.000 -1.
STORAGE= 0. 57. 143. 260. 406. 790. 1437. 2091. 2462. 0.
OUTFLOW= 0. 413. 1191. 1375. 2379. 6241. 25057. 42240. 51938. 0.

STATION 2, PLAN 1, RTIO 1
0. 0. 7. 24. 66. 151. 324. 684. 1202.
1343. 1970. 2752. 3448. 3833. 3966. 3917. 3740. 3192.
2891. 2597. 2336. 2147. 1958. 1774. 1600. 1436. 1313.
1270. 1225. 1132. 914. 747. 618. 517. 436. 331.
291. 255. 224. 197. 173. 152. 133. 117.

STOR
0. 0. 1. 3. 9. 21. 44. 87. 150.
240. 347. 443. 513. 564. 559. 541. 516. 487.
457. 428. 400. 373. 345. 318. 293. 245. 220.
193. 165. 137. 112. 94. 79. 69. 59. 45.
40. 35. 31. 27. 24. 21. 18. 16.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
38624. 29135. 10497. 503850.
CFS 9.03 13.02 13.02 13.02
INCHES 14455. 20831. 20831. 20831.
AC-FT

0.	0.	2.	13.	49.	132.	303.	695.	1240.	1763.
3291.	5083.	6960.	8899.	9070.	8599.	7683.	7075.	6268.	5910.
5271.	4998.	4505.	4038.	3600.	3198.	2833.	2505.	2259.	2059.
1865.	1681.	1509.	1369.	1331.	1209.	1245.	1199.	997.	811.
667.	555.	467.	398.	349.	306.	268.	235.		
0.	0.	0.	2.	7.	18.	41.	88.	174.	316.
497.	675.	814.	881.	887.	871.	845.	818.	791.	757.
713.	666.	617.	571.	528.	488.	452.	419.	389.	360.
331.	305.	279.	256.	232.	205.	177.	148.	122.	101.
85.	72.	63.	55.	48.	42.	37.	32.		
STOR									
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
CFS 9070. 6726. 2609. 125234.									
INCHES 2.09 3.24 3.24 3.24									
AC-FT 3337. 5178. 5178. 5178.									
STATION 2, PLAN 1, RTIO 3									
0.	0.	3.	20.	73.	198.	462.	1080.	1433.	3125.
5613.	10216.	13131.	14020.	13773.	12940.	11835.	10615.	9602.	8281.
7236.	6406.	5961.	5535.	5058.	4573.	4103.	3661.	3254.	2884.
2551.	2288.	2088.	1893.	1708.	1534.	1374.	1237.	1096.	952.
1206.	1033.	838.	688.	571.	479.	407.	356.		
0.	0.	0.	3.	10.	27.	62.	131.	268.	480.
727.	926.	1027.	1057.	1049.	1020.	982.	940.	898.	860.
826.	795.	762.	720.	672.	624.	578.	534.	493.	457.
423.	393.	364.	335.	308.	283.	259.	236.	209.	182.
153.	126.	104.	87.	74.	64.	56.	49.		
STOR									
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
CFS 14020. 10322. 3913. 187842.									
INCHES 3.20 4.85 4.85 4.85									
AC-FT 5121. 7766. 7766. 7766.									
STATION 2, PLAN 1, RTIO 4									
0.	0.	4.	26.	98.	264.	643.	1245.	2070.	4643.
9826.	15141.	17887.	18789.	18388.	17250.	15781.	14153.	12536.	11044.
9715.	8582.	7509.	6601.	6040.	5636.	5168.	4684.	4209.	3760.
3345.	2967.	2625.	2335.	2135.	1938.	1750.	1573.	1409.	1245.
1305.	1282.	1216.	1086.	877.	719.	595.	498.		
0.	0.	1.	4.	13.	36.	92.	177.	361.	631.
906.	1096.	1191.	1222.	1208.	1169.	1118.	1062.	1006.	955.
909.	869.	833.	802.	770.	730.	683.	635.	588.	543.
502.	465.	431.	400.	371.	342.	315.	289.	265.	241.
215.	188.	159.	131.	108.	91.	77.	66.		
STOR									
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
CFS 18789. 14072. 5214. 250443.									
INCHES 4.36 6.47 6.47 6.47									
AC-FT 6981. 10354. 10354. 10354.									
STATION 2, PLAN 1, RTIO 5									
0.	0.	5.	33.	122.	330.	823.	1321.	2867.	6137.
14362.	19506.	22503.	23522.	22994.	21577.	19727.	17692.	15670.	13805.
12143.	10677.	9387.	8252.	7254.	6377.	5949.	5519.	5042.	4557.
4087.	3646.	3241.	2872.	2539.	2281.	2081.	1886.	1701.	1528.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

10078	11400	10078	10000	10000	10000	10000	10000	10000	10000
993.	942.	859.	824.	794.	761.	718.	671.	622.	575.
576.	532.	492.	455.	422.	392.	363.	334.	307.	282.
259.	235.	208.	181.	152.	125.	103.	87.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
23522.	17846.	6521.	312987.	
CFS	5.53	8.09	8.09	
INCHES	8854.	12940.	12940.	
AC-FT				

STATION 2, PLAN 1, RTIO 6

0.	0.	6.	39.	147.	395.	1004.	1463.	3761.	9144.
17802.	23552.	26920.	28126.	27602.	25999.	23760.	21252.	18810.	16568.
14573.	12813.	11264.	9902.	8705.	7653.	6727.	6091.	5701.	5239.
4755.	4277.	3824.	3404.	3020.	2673.	2366.	2165.	1967.	1778.
1599.	1433.	1351.	1311.	1268.	1223.	1119.	902.		

STOR

0.	0.	1.	5.	20.	54.	122.	273.	544.	898.
1188.	1386.	1508.	1554.	1534.	1473.	1393.	1306.	1222.	1145.
1076.	1016.	983.	916.	874.	838.	806.	775.	736.	690.
642.	595.	558.	508.	478.	436.	405.	375.	346.	319.
293.	268.	244.	219.	192.	163.	135.	111.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
28126.	21481.	7822.	7822.	375452.
CFS	6.66	9.70	9.70	
INCHES	10657.	15523.	15523.	
AC-FT				

STATION 2, PLAN 1, RTIO 7

0.	0.	6.	46.	121.	471.	1182.	1761.	4599.	12193.
21150.	27419.	31282.	32777.	32191.	30329.	27812.	24996.	21996.	19342.
17004.	14949.	13141.	11553.	10156.	8928.	7848.	6900.	6160.	5790.
5336.	4852.	4371.	3912.	3484.	3093.	2738.	2420.	2204.	2005.
1814.	1633.	1464.	1358.	1319.	1276.	1232.	1164.		

STOR

0.	0.	1.	6.	23.	63.	142.	316.	627.	995.
1303.	1527.	1674.	1731.	1709.	1638.	1542.	1435.	1332.	1241.
1160.	1089.	1027.	972.	924.	882.	845.	812.	782.	745.
700.	652.	604.	559.	516.	477.	442.	410.	381.	352.
324.	297.	273.	249.	224.	197.	169.	140.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
32777.	25104.	9121.	9121.	437827.
CFS	7.78	11.31	11.31	
INCHES	12455.	18101.	18101.	
AC-FT				

STATION 2, PLAN 1, RTIO 8

0.	0.	7.	52.	196.	549.	1225.	2091.	5471.	15291.
24510.	31197.	35710.	37448.	36786.	34661.	31785.	28571.	25349.	22176.
19452.	17049.	15020.	13203.	11607.	10203.	8970.	7885.	6932.	6173.
5807.	5354.	4870.	4389.	3928.	3499.	3106.	2750.	2431.	2211.
2012.	1820.	1639.	1470.	1360.	1320.	1278.	1233.		

STOR

0.	0.	1.	7.	27.	72.	165.	364.	713.	1101.
1419.	1671.	1842.	1908.	1883.	1802.	1633.	1571.	1448.	1338.
1244.	1163.	1092.	1029.	974.	926.	884.	846.	813.	783.
747.	702.	654.	606.	560.	518.	479.	441.	412.	382.
353.	325.	298.	274.	250.	225.	198.	170.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
32777.	25104.	9121.	9121.	437827.
CFS	7.78	11.31	11.31	
INCHES	12455.	18101.	18101.	
AC-FT				

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

STATION		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9	
0.	0.	9.	66.	245.	707.	1236.	2903.	8260.	20600.
30645.	3997.	4614.	46792.	45992.	43330.	39780.	35716.	31697.	27941.
24557.	21622.	19790.	16508.	14509.	12754.	11212.	9856.	8665.	7617.
6696.	6078.	5685.	5222.	4737.	4261.	3808.	3389.	3007.	2661.
2359.	2158.	1960.	1771.	1593.	1427.	1349.	1309.		

STOR		24-HOUR		72-HOUR		TOTAL VOLUME	
0.	0.	1.	9.	34.	89.	210.	458.
1650.	1966.	2182.	2265.	2234.	2133.	1996.	1843.
1420.	1312.	1222.	1143.	1074.	1014.	961.	914.
805.	773.	734.	688.	640.	593.	548.	507.
403.	374.	345.	318.	292.	267.	246.	218.

PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	46792.	35949.	13018.	13018.	16.15	16.15	16.15	624858.	
INCHES		11.15	16.15	16.15					
AC-FT		17835.	25834.	25834.				25834.	

STATION		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9		2, PLAN 1, RTIO 9	
0.	0.	9.	66.	245.	707.	1236.	2903.	8260.	20600.
30645.	3997.	4614.	46792.	45992.	43330.	39780.	35716.	31697.	27941.
24557.	21622.	19790.	16508.	14509.	12754.	11212.	9856.	8665.	7617.
6696.	6078.	5685.	5222.	4737.	4261.	3808.	3389.	3007.	2661.
2359.	2158.	1960.	1771.	1593.	1427.	1349.	1309.		

STOR		24-HOUR		72-HOUR		TOTAL VOLUME	
0.	0.	1.	9.	34.	89.	210.	458.
1650.	1966.	2182.	2265.	2234.	2133.	1996.	1843.
1420.	1312.	1222.	1143.	1074.	1014.	961.	914.
805.	773.	734.	688.	640.	593.	548.	507.
403.	374.	345.	318.	292.	267.	246.	218.

PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	46792.	35949.	13018.	13018.	16.15	16.15	16.15	624858.	
INCHES		11.15	16.15	16.15					
AC-FT		17835.	25834.	25834.				25834.	

A-34

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

814.	303.	720.	470.	408.	923.	340.	308.
263.	232.	184.	166.	154.	144.	127.	115.
101.	88.	66.	57.	50.	44.	39.	
					</		

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

0.	0.	1.	5.	23.	82.	301.	631.	1333.	3059.
6916.	14512.	20968.	24985.	26754.	26782.	25614.	23709.	21455.	19148.
16956.	15031.	13327.	11765.	10364.	9120.	8115.	6006.	6560.	6006.
5491.	4936.	4515.	4231.	3982.	3704.	3414.	3133.	2872.	2524.
2228.	1975.	1768.	1613.	1498.	1409.	1324.	1213.		

0.	0.	0.	1.	4.	13.	34.	66.	133.	309.
660.	1072.	1381.	1569.	1652.	1653.	1598.	1509.	1404.	1296.
1194.	1098.	1010.	929.	856.	792.	733.	680.	638.	605.
574.	544.	514.	483.	446.	405.	362.	320.	282.	247.
219.	195.	175.	160.	149.	141.	132.	122.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
26782.	20770.	7764.	7764.	372661.
3FS	6.44	9.63	9.63	
INCHES				
AC-FT	10304.	15407.	15407.	

0.	0.	1.	6.	27.	105.	360.	754.	1614.	3659.
9555.	19087.	24988.	29314.	31261.	31261.	29915.	27758.	25140.	22400.
19810.	17461.	15416.	13668.	12066.	10629.	9353.	8299.	7399.	6675.
6110.	5593.	5094.	4610.	4274.	4033.	3759.	3471.	3187.	2923.
2592.	2284.	2023.	1806.	1640.	1519.	1425.	1344.		

0.	0.	0.	1.	5.	15.	40.	78.	160.	398.
814.	1246.	1569.	1771.	1862.	1862.	1799.	1698.	1576.	1448.
1327.	1217.	1118.	1028.	945.	870.	804.	744.	689.	645.
611.	580.	549.	520.	489.	454.	413.	370.	328.	289.
254.	224.	199.	179.	163.	151.	142.	134.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
31261.	24401.	9056.	9056.	434666.
3FS	7.57	11.23	11.23	
INCHES				
AC-FT	12106.	17971.	17971.	

0.	0.	1.	7.	31.	128.	397.	844.	1885.	4265.
12459.	21620.	28891.	33610.	35737.	35737.	34199.	31729.	28799.	25705.
22706.	19988.	17578.	15494.	13735.	12124.	10680.	9398.	8333.	7428.
6697.	6129.	5612.	5112.	4627.	4282.	4042.	3770.	3461.	3198.
2932.	2605.	2295.	2032.	1813.	1645.	1522.	1428.		

0.	0.	0.	1.	6.	18.	43.	86.	186.	489.
965.	1412.	1751.	1971.	2072.	2071.	1999.	1883.	1747.	1603.
1463.	1335.	1223.	1122.	1031.	948.	873.	806.	746.	691.
647.	612.	581.	551.	521.	491.	455.	415.	372.	330.
290.	255.	225.	200.	179.	163.	151.	142.		

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
35757.	28026.	10349.	10349.	496740.
3FS	8.69	12.84	12.84	
INCHES				
AC-FT	13904.	20537.	20537.	

0.	0.	1.	9.	39.	175.	468.	1046.	2655.	6899.
17418.	28077.	36483.	42086.	44700.	44676.	42770.	39706.	36057.	32232.
28557.	25137.	22054.	19355.	16998.	15012.	13288.	11720.	10320.	9080.
8083.	7220.	6540.	5987.	5475.	4978.	4498.	4221.	3972.	3694.
3404.	3124.	2864.	2512.	2218.	1967.	1761.	1608.		

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

1613.	1713.	1400.	1306.	1196.	1097.	1008.	854.	1707.
1736.	1576.	1432.	1306.	1196.	1097.	1008.	854.	789.
731.	678.	637.	604.	573.	542.	513.	445.	403.
360.	319.	280.	246.	218.	194.	174.	160.	
PEAK								
6-HOUR								
24-HOUR								
72-HOUR								
TOTAL VOLUME								
SFS								
INCHES								
AC-FT								
44700.								
35211.								
12941.								
12941.								
16.05								
16.05								
17469.								
25680.								
25680.								
25680.								

PEAK FLOW SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS

OPERATION	STATION	PLAN	RATIOS APPLIED TO FLOWS							
			.10	.20	.30	.40	.50	.60	.70	.80 1.00
HYDROGRAPH AT	1	1	4828.	9656.	14484.	19312.	24140.	28968.	33796.	38624.
	2	2	0.	0.	0.	0.	0.	0.	0.	48288.
ROUTED TO	2	1	3966.	9070.	14020.	18789.	23522.	28126.	32777.	37448.
	2	2	0.	0.	0.	0.	0.	0.	0.	46792.
ROUTED TO	3	1	3441.	8059.	12990.	17672.	22262.	26782.	31261.	35757.
	2	2	0.	0.	0.	0.	0.	0.	0.	44700.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC